LIST OF FURNITURE REQUIRED FOR CHIKJAJUR-CHITALDRUG RAILWAY.

No.	Particulars	Size, etc.	No. required.
1	Almirahs	6′X4′X18″ B. H.	3
2	Benches for 3rd class Waiting rooms ...	7′X1½′X1½′	10
3	Boxes (parcel)	4′X3′X2½′	3
4	Boards (Fare table)	2½′X2½′X1″	3
5	Boards (Glazed, foolscap size, for Station to Station Fares).	1½′X1½′ in frame	3
6	Boards (loading)	12′X15″X1¼″	4
7	Chairs, Bug-proof		8
8	Ladder (wooden)	5′ high X1½′	3
9	Shelves (Wall, wooden)	6′X1½′X4″	3
10	Stools (office, T. W.)	1½′ dia. X2½′ high	7
11	Tables with Cub-board	6′X3′ (for telegraphic instruments)	3
12	Table with two drawers	5′X3′	3
13	Table with two drawers	4½′X2½′	3
14	Ticket counters	8¾′X2′X3½′	3
15	Ticket cases (single)		2
16	„ „ (double)	3¾′X2½′X10′ (three compartments)	1
17	Table, round	4½′ dia. X2½′ high	1
18	Table with two drawers	4½′X2½′ Ornamental	1
19	Mirror with stand		1
20	Hat-rack		1
21	Chairs, Rattan ...		4
22	„ (Lounging) Rattan		1
23	Benches with rattan seats with backs ...	6½′X2′X1½′ with back of 1¾′ high	2

K. SREENIVASA IYENGAR,
Offg. Superintending Engineer,
Mysore Railways.

CITY IMPROVEMENT DIVISION, BANGALORE.

Notice dated 14th December 1920.

Notice is hereby given that sealed tenders for improving the main drain running through the general market will be received in person by the Executive Engineer, City Improvement Division, Bangalore, at his office in V Main road, Chamarajpet, up to 4 P.M. on 15th January 1921. An approximate schedule of quantities and rates as sanctioned is given below. The quantities are to be taken as approximate only subject to alteration. The work should be completed by the end of May 1921.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, between 12 noon and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained at the Office of the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items of work specified will be executed or at what per cent below or above the estimate it will be executed. Rates should be quoted only for units shown in the schedule. Quotations for new units will not be considered.

4 Each tender must be accompanied by a deposit of Rs. 1,000 (one thousand) in cash or currency notes as earnest money and be superscribed " Tender for Removing the Kink of the City Main Drain on the Avenue road and regrading and covering portion of it running through the Market," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the City Improvement Committee, which does not bind itself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted will be posted on the notice board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money forfeited without further reference to him.

8. On the final disposal of tenders, the earnest money on rejected tenders will be

returned to the tenderers on their applying to the Executive Engineer in person or through their accredited Agents.

Abstract.

Items of work	Per	Rate	Quantity	Cost
		Rs. a. p.		Rs.
Earthwork excavation	C. yd.	0 4 0	2,714	679
Old stone in surki mortar	C. ft.	0 3 6	8,894	1,949
Removing old slabs of the existing drain ...	Sqr.	2 0 0	270·74	541
Flooring the bed of drain with old slabs on 3" surki concrete including cement pointing.	Do	25 0 0	258·20	6,455
Rolled steel girders including Railway freight, carriage, fixing, tarring 2 coats, etc., complete.	Cwt.	24 0 0	1,233	29,592
Burnt stone slabs, 6" thick	S. ft.	0 7 0	19,424	8,498
Burnt stone slabs, 4" thick	Do	0 5 0	6,000	1,875
Cement pointing, 1" deep	Do	5 0 0	38·89	194
Dismantling and removing the existing masonry...	C. ft.	0 0 6	11,918	372
Removing the covering slabs over existing culverts	Sqr.	3 0 0	13·02	39
Constructing cement concrete drain including cement and plastering.	C. ft.	1 10 0	1,757	2,855
Earthwork, filling old drain with available earth...	C. yd.	0 4 0	2,709	677
Fixing cast iron gratings (3" x 4") for ventilation...	Each	100 0 0	2	200
Total		...	...	53,923
Deduct cost of old materials:—Size stone ...	C. ft.	0 1 0	641	40
Burnt stone slabs	S. ft.	0 2 0	2,556	319
Total deductions		...	..	359
Balance amount of estimate ...		...	...	53,564

T. RAMACHANDRA ROW,
Executive Engineer.

SANITARY DIVISION.

Dated 16th December 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary Division, up to 10th January 1921, for Cast Iron Pipes and specials. An approximate estimate of quantities is given below. These quantities are not guaranteed.

2. Tenders should be submitted on printed Forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rupees one hundred in cash or Government Promissory Notes as earnest money and be superscribed as "Tender for Cast Iron Pipes and specials for Improving the water-supply to Chintamani Town", in default of which tenders will be rejected.

4. The final acceptance of the tender will rest with the Superintending Engineer Sanitary Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

5. Within 8 days of the accepted tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be cancelled and his earnest money forfeited.

6. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned

8. The tender should be *for delivery F. O. R. Chintamani Railway Station*, Mysore Railways, Narrow Gauge.

9. The supply should be completed within a month from the date of placing the orders.